



ST. THERESE

CONSTRUCTION DOCUMENTS

Shrine of St. Therese CHAPEL RENOVATION



Diocese of Juneau

STRUCTURAL PND, INC. 3220 HOSPITAL DRIVE, STE. 200 JUNEAU, ALASKA 99801 907-586-2093 FAX 907-586-2099 EMAIL cgianotti@pnd-jnu.com	MECHANICAL MURRAY & ASSOCIATES, P.C. P.O. BOX 21081 JUNEAU, ALASKA 99802-1081 907-780-6151 FAX 907-780-6182 EMAIL doug@murraypc.com	ELECTRICAL GORMAN ENGINEERS 800 GLACIER AVE., STE. E JUNEAU, ALASKA 99801 907-463-6721 FAX 907-586-6216 EMAIL pgorman@gci.net	ABESTOS ABATEMENT CARSON DORN, INC. 712 W, 12TH STREET JUNEAU, ALASKA 99801 907-586-4447 FAX 907-586-5917 EMAIL tcarson@carsondorn.com	OWNER CATHOLIC DIOCESE OF JUNEAU 415 6TH STREET JUNEAU, ALASKA 99801 907-586-2227
---	---	---	--	---

A.E. Rogers

ARCHITECTS, LLC

P.O. Box 34401 • Juneau, Alaska 99803
Tele 907.789.7589 Fax 907.789.1638

EMAIL alan@aerogers.com

ABBREVIATIONS

NOTE: THIS IS A GENERIC LIST. NOT ALL ABBREVIATIONS ARE USED IN DRAWINGS

AB ANCHOR BOLTS	(E) EXISTING TO REMAIN	MTD MOUNTED	REQ REQUIRED
ACOUS ACUSTICAL	EXIST EXISTING	MTL METAL	RESIL RESILIENT
ACM ACUSTICAL CONTAINING MATERIAL	EXT EXTERIOR	MUL MULLION	RGR REGISTER
ACT ACUSTICAL CEILING TILE	FA FIRE ALARM	N NORTH	RM ROOM
AFF ABOVE FINISH FLOOR	FD FLOOR DRAIN	N NOT IN CONTRACT	RO ROUGH OPENING
AL ALUMINUM	FE FIRE EXTINGUISHER	NO OR # NUMBER	RO SCHEDULE
ARCH ARCHITECTURAL	FHC FIRE HOSE CABINET	NOM NOMINAL	SD SOAP DISPENSER
ASB ASBESTOS	FIN FINISH	NTS NOT TO SCALE	SM SIMILAR
ASPH ASPHALT	FL FLOOR	OVERALL OVERALL	SPEC SPECIFICATIONS
BD BOARD	FDC FACE OF CONCRETE	OBS OBSOLETE	STC SOUND TRANSMISSION CLASS
BITUM BITUMINOUS	FOF FACE OF FINISH	OC ON CENTER	STD STANDARD
BLDG BUILDING	FOS FACE OF STUDS	OD OUTSIDE DIAMETER	STL STEEL
BOD BOTTOM OF DECK	FT FOOT OR FEET	OD OWNER FURNISH	STRUC STRUCTURAL
CB CATCH BASIN	FURR FURRING	CONTRACTOR INSTALL	SS STAINLESS STEEL
CG CORNER GUARD	FUT FUTURE	OFF OFFICE	TOWL TOWEL BAR
CI CAST IRON	GA GAUGE	OFDI OWNER FURNISH	TC TOP OF CURB
CLG CEILING	GALV GALVANIZED	OWNR OWNER INSTALL	TEL TELEPHONE
CLR CLEAR	GB GRAB BAR	OPNG OPENING	TER TERRAZZO
COL COLUMN	GL GLASS	OPP OPPOSITE	TJL TRUSS JOIST
CONC CONCRETE	GR GRADE	OSB ORIENTED STAND BOARD	TOD TOP OF DECK
CORR CORR	GYP GYPSUM	PIC PLASTIC IMPREGNATED CORK	TPD TOILET PAPER DISPENSER
CRFT CRFT	GWB GYPSUM WALL BOARD	PL PLATE	TS TUBE STEEL
DEPT DEPARTMENT	H HIGH	PLM PLASTIC LAMINATE	TV TELEVISION
DF DRINKING FOUNTAIN	HB HOSE BIBB	PLYWD PLYWOOD	TYP TYPICAL
DET DETAIL	ACCESSIBLE TO DISABLED	PR PAIR	UL UNDERWRITER LABORATORY
DIA DIAMETER	HWDH HARDWOOD	PRCST PRE-CAST	UNLESS OTHERWISE NOTED
DIM DIMENSION	HT HEIGHT	PT PRESSURE TREATED	VEST VESTIBULE
DN DOWN	HM HOLLOW METAL	PTD PAINTED	VENT VENT THROUGH ROOF
DS DOWNSPOUT	INSUL INSULATION	PTH PARTITION	VTR WATER CLOSET
DWG DRAWING	JAN JANITOR	PVC POLY VINYL CHORIDE	WC WOOD
EA EACH	LAV LAVATORY	QT QUARRY TILE	WP WATERPROOF
EL ELEVATION	LT LIGHT	R RISER	WR WATER RESISTANT
ELEC ELECTRICAL	MAX MAXIMUM	RAD RADIUS	WSCOT WAHNSCOT
ELEV ELEVATOR	M/E MECHANICAL AND ELECTRICAL	RD ROOF DRAIN	WT WEIGHT
EP ELECTRICAL PANELBOARD	MECH MECHANICAL	REF REFERENCE	REMOVE REMOVE
EQ EQUAL	MIN MINIMUM	REFR REFRIGERATOR	
EQUIP EQUIPMENT	MISC MISCELLANEOUS	REINF REINFORCED	

DRAWING LEGEND

BUILDING SECTION		SECTION NUMBER
EXTERIOR ELEVATION		ELEVATION NUMBER
WALL SECTION		SECTION NUMBER
DETAIL REFERENCE		DETAIL NUMBER
INTERIOR ELEVATIONS		ELEVATION NUMBER
		NEW CONSTRUCTION
		ITEMS TO BE REMOVED
		EXISTING ITEMS TO REMAIN

RESPECT FOR THE SHRINE

THE SHRINE OF ST. THERESE IS CONSIDERED A HOLY PLACE BY MANY. ALL WORKERS ON THE SHRINE SITE ARE ASKED TO RESPECT THE RULES OF THE SHRINE (POSTED ON THE SITE).

THE CHAPEL CRYPT, LOCATED BELOW THE FLOOR UNDER THE EXISTING ALTAR, IS THE BURIAL SITE OF TWO BELOVED BISHOPS. THE CRYPT SHALL REMAIN IN PLACE AND IT IS REQUESTED THAT ALL WORK AROUND THE CRYPT BE DONE WITH AS LITTLE DISRUPTION AS POSSIBLE AND THAT THE WORKERS RESPECT THE SANCTITY OF THE BURIAL SITE.

DRAWING SCHEDULE

ARCHITECTURAL	M3 FLOOR PLANS
A0 CODE INFORMATION SYMBOLS & ABBREVIATIONS	M4 BUILDING SECTION, BUILDING ELEVATIONS, ENLARGED PLAN
S1 ISLAND SITE PLAN (EXIST.)	M5 DETAILS, DIAGRAMS, SPECIFICATIONS
A1 DEMOLITION FLOOR PLANS	M6 SPECIFICATIONS
A2 DEMOLITION ROOF PLAN	M7 CONTROLS
A3 NEW WORK FLOOR PLANS	
A4 NEW WORK ROOF PLAN	ELECTRICAL
A5 BUILDING SECTION & EXTERIOR ELEVATIONS	E1 LEGEND, NOTES, TRENCH DETAIL, SINGLE LINE DIAGRAMS
A6 WINDOW TYPES & EXTERIOR ELEVATIONS	E2 SITE LIGHTING PLAN
A7 DETAILS	E3 DEMOLITION PLAN
A8 DETAILS	E4 CHAPEL POWER PLAN
A9 DETAILS	E5 CHAPEL LIGHTING PLAN
A10 SCHEDULES	E6 SCHEDULES, CHOIR LOFT PLAN
A11 DOOR PHOTOS	E7 LUMINAIRE SCHEDULE, EXTERIOR LIGHTING, CONTROL SCHEMATIC
A12 INTERIOR ELEVATIONS	E8 SPECIFICATIONS
A13 SPECIFICATIONS	E9 SPECIFICATIONS
MECHANICAL	ASBESTOS ABATEMENT
M1 SCHEDULES, SYMBOLS	NO DRAWINGS (SEE SPECIFICATIONS)
M2 DEMOLITION FLOOR PLAN	



IBC CODE REVIEW

CODE: INTERNATIONAL BUILDING CODE (IBC) 2000

OCCUPANCY: A-3 (ASSEMBLY)

OCCUPANCY SEPARATIONS: NONE

CONSTRUCTION TYPE: TYPE III-B

OCCUPANT LOAD: CHAPEL = 90 OCCUPANTS (PEWS)
BALCONY = 19 OCCUPANTS (UNFIXED CHAIRS)
TOTAL = 109 OCCUPANTS

AUTOMATIC SPRINKLER SYSTEM: BUILDING IS NOT SPRINKLERED

BUILDING CODE SUMMARY

SOURCE: INTERNATIONAL BUILDING CODE, 2000 EDITION
UNIFORM MECHANICAL CODE, 2000 EDITION
UNIFORM PLUMBING CODE, 2000 EDITION
NEC, 1999
NFPA 13, 2000 EDITION
NFPA 101, 2000 EDITION
NFPA 99, 1999 EDITION
AMERICANS WITH DISABILITIES ACT ACCESSIBILITY GUIDELINES (ADAAG)


GENERAL NOTES

- ALL CONSTRUCTION TO BE PER 2000 IBC AND ALL APPLICABLE MECHANICAL, ELECTRICAL, FIRE CODES (AS AMENDED BY THE CBJ) AND THE CBJ ZONING/LAND USE REQUIREMENTS. THE CONSTRUCTION WILL BE IN ACCORDANCE WITH THE ADAAG (AMERICANS WITH DISABILITIES ACT - ACCESSIBILITY GUIDELINES).
- ALL INTERIOR WALLS & FURRING ARE TO BE GALVANIZED METAL FRAMING UNLESS OTHERWISE NOTED. DIMENSIONS ARE TO FACE OF FRAMING MEMBER UNLESS OTHERWISE NOTED.
- CONTRACTOR TO VERIFY ALL EXISTING CONDITIONS AND DIMENSIONS BEFORE BEGINNING WORK AND TO NOTIFY THE OWNER'S REPRESENTATIVE AS TO ANY DISCREPANCIES.
- DISPOSAL OF DEMOLITION MATERIAL (NOT BE SALVAGED) IS THE RESPONSIBILITY OF THE CONTRACTOR. BURNING AND DISPOSAL OF CONCRETE AND EXCAVATED MATERIAL WILL BE ALLOWED ON THE SHRINE PROPERTY IN AN AREA DESIGNATED BY THE OWNER.
- REMOVE ALL ELECTRICAL OUTLETS, TELEPHONE JACKS, SWITCHES AND THERMOSTATS THAT ARE LOCATED IN INTERIOR WALLS TO BE REMOVED OR WALLS WHERE A CONFLICT WITH NEW WORK EXISTS. IF UTILITIES ARE NOT TO BE EXTENDED, CAP IN A SAFE MANNER IN ACCORDANCE WITH ACCEPTED INDUSTRY STANDARDS.
- WHERE REMOVAL OF EXISTING CONDITIONS HAS OCCURRED, PATCH AS REQUIRED TO MATCH EXISTING ADJACENT SURFACES AND FINISHES.
- CONTRACTOR SHALL PROVIDE A MINIMUM OF 24 HOURS NOTICE PRIOR TO SHUTTING OFF ANY SYSTEM. CONTACT THE SHRINE CARETAKER AT 789-9815.
- THESE DRAWINGS ARE FOR USE ON THE SHRINE OF ST. THERESE CHAPEL RENOVATION PROJECT ONLY. THEY ARE NOT TO BE REUSED IN WHOLE OR IN PART ON ANY OTHER PROJECT WITHOUT WRITTEN PERMISSION FROM A.E. ROGERS ARCHITECTS, LLC.

CBJ BLDG. PERMIT NO.
BLD2003-00762

DECEMBER 15, 2003

CODE INFORMATION SYMBOLS & ABBREVIATIONS



A0