



A ROOF PLAN
 SCALE: 1/4" = 1'-0"
 D:\CAD\0302

SHEET NOTES

- 15 REMOVE EXIST. ROOF SURFACE, DECK AND STRUCTURE.
- 16 REMOVE EXIST. WOODEN SHINGLES, FLASHING AND UNDERLAYMENT TO EXPOSE EXIST. ROOF DECK. PREP TO RECEIVE NEW ROOFING.
- 17 REMOVE EXIST. EXHAUST STACK (SEE MECHANICAL).
- 18 REMOVE EXIST. ROOFING, ROOF DECK AND ROOF STRUCTURE. PREPARE FOR INSTALLATION OF NEW ROOF STRUCTURE.

DEMOLITION NOTES

- 1. SEE MECHANICAL AND ELECTRICAL DRAWINGS FOR ADDITIONAL DEMOLITION WORK & COORDINATION.
- 2. PREPARE EXISTING SURFACES TO RECEIVE NEW WORK.
- 3. ITEMS TO BE REMOVED ARE THE PROPERTY OF THE CONTRACTOR UNLESS OTHERWISE NOTED.
- 4. SEE "GENERAL NOTES" ON SHEET A0.
- 5. COORDINATE ALL DEMOLITION WORK WITH ASBESTOS ABATEMENT (SEE ABATEMENT DOCUMENTS).

ASBESTOS ABATEMENT

- 1. THE FOLLOWING MATERIALS HAVE BEEN SHOWN TO BE ASBESTOS CONTAINING MATERIALS (ACM) AND WILL NEED TO BE ABATED AS PART OF THIS PROJECT:
 - A. "SPARKLY" SURFACING FINISH THAT IS FOUND ON MANY INTERIOR PLASTER WALLS
 - B. GLAZING MATERIAL HOLDING GLASS IN ORIGINAL MULTI-PANED METAL-FRAMED WINDOWS.
- 2. THE FOLLOWING MATERIALS HAVE BEEN SHOWN TO BE NON-ACM, SO THEY NEED NOT BE ABATED:
 - A. PLASTER SUBSTRATE ON INTERIOR WALLS, AND
 - B. TARPAPER UNDERLYING EXISTING ROOFING MATERIALS
- 3. ABATEMENT OF ACM SHALL BE DONE IN ACCORDANCE WITH SPECIFICATION SECTION 02080.

A.E. Rogers
 ARCHITECTS, LL
 P.O. Box 34401 • Juneau, Alaska 998
 Tele 907.789.7589 Fax 907.789.16



CBJ BLDG. Permit No. BLD2003-00762

CONSTRUCTION DOCUMENTS
Shrine of St. Therese
CHAPEL RENOVATION
 Catholic Diocese of Juneau
 419 6th Street
 Juneau, Alaska 99801

Number	Date	By	Description of Revisions

Sheet Title
DEMOLITION ROOF PLAN

Scale AS SHOWN (11 X 17 = HALF SCALE)

Designed AER Drawn AER
 Date DEC. 15, 2003 Checked AER
 Approved By AER Job Number 0302

