



SHEET NOTES

- 1 SUPPLY & INSTALL NEW 1X6 T&G CEDAR PANELING ON WALLS AND CEILING. SEE DETAIL E/A9.
- 2 REINSTALL SALVAGED MIRROR.
- 3 REINSTALL EXISTING PEWS.
- 4 NEW DRAIN TILE & GRAVEL BACKFILL. EXTEND ALONG ENTIRE ROOF DRIP EDGE. RUN DRAIN TILE TO DAYLIGHT. SEE DETAIL E/A7.
- 5 INSERT 6" OF EXTRUDED POLYSTYRENE RIGID INSULATION INTO CHIMNEY FLUE TO PREVENT DRAFTS. CAP TOP OF CHIMNEY TO PREVENT AIR DRAFTS, WATER/MOISTURE FROM PENETRATING.
- 6 NEW INSULATED FURRED WALLS. TYPICAL ON ALL INTERIOR WALLS WITH EXTERIOR EXPOSURE. SEE DETAIL F/A7.
- 7 INSTALL 29"X32" ACCESS PANEL. APPLY 4" OF RIGID INSULATION TO MECH. ROOM SIDE.
- 8 DRILL ACCESS THROUGH EXISTING CONCRETE WALL FOR MECHANICAL DUCTWORK. SEE MECH. DWGS. FOR LOCATION AND SIZE.

A.E. Roger
 ARCHITECTS, LL
 P.O. Box 34401 • Juneau, Alaska 998
 Tele 907.789.7589 Fax 907.789.16



CBJ BLDG. Permit No. BLD2003-00762

CONSTRUCTION DOCUMENTS
Shrine of St. Therese
CHAPEL RENOVATION
 Catholic Diocese of Juneau
 419 6th Street
 Juneau, Alaska 99801

Number	Date	By	Description of Revisions

Sheet Title
NEW WORK FLOOR PLANS

Scale AS SHOWN (11 X 17 = HALF SCALE)
 Designed AER Drawn AER
 Date DEC. 15, 2003 Checked AER
 Approved By AER Job Number 0302

